

GENERAL NOTES:

- CONTRACTOR IS RESPONSIBLE FOR ALL INTERSTITIAL PATCHING AND PENETRATIONS REQUIRED.
- ALL SATELLITE SPD ROOMS TO BE BALANCED TO HAVE A POSITIVE PRESSURE TO ADJACENT ROOM.
- CONTRACTOR TO MEASURE AIRFLOW QUANTITIES AT ALL DIFFUSERS AND GRILLES IN SATELLITE SPD ROOMS BEFORE AND AFTER WORK. CONTRACTOR TO VERIFY CONSTRUCTION WORK OR BALANCING SHALL NOT IMPACT AIRFLOW QUANTITIES OF DIFFUSERS AND GRILLES IN ROOMS SERVED BY THE SAME VAV BOX. SEE VAV BOX BALANCING SCHEDULE ON SHEET FOR LIST OF ROOMS SERVED BY THE SAME VAV.
- DIFFUSERS LABELED "CFM, EXISTING" DENOTE AN EXISTING DIFFUSER TO BE BALANCED TO CFM INDICATED.

KEY NOTES:

- ① RE-BALANCE DIFFUSER TO CFM INDICATED.
- ② BALANCE EXISTING BOX TO NEW CFM TOTAL INDICATED ON PLAN. VAV BOX TO CONSTANT VOLUME.
- ③ INSTALL NEW CEILING DIFFUSER.
- ④ DEMOLISH EXISTING DIFFUSER.
- ⑤ INSTALL NEW RETURN GRILLE.
- ⑥ 6" SUPPLY DUCT DOWN.
- ⑦ RE-BALANCE VAV BOX MINIMUM AND MAXIMUM AIRFLOW QUANTITIES BY THE QUANTITY INDICATED IN THE VAV BOX SCHEDULE ON SHEET. VAV BOX TO BE CONSTANT VOLUME.

VAV BOX BALANCING SCHEDULE

VAV BOX NUMBER	ROOM SERVED	CHANGE IN TOTAL BOX CFM	MECH NOTES
VAV-2-1	2F-108	+70 CFM	1
VAV-2-2	2J-147, C2-75	+50 CFM	1
VAV-2-3	2K-110	+60 CFM	1
VAV-2-4	2K-131	+70 CFM	1
VAV-2-5	2P-103	+55 CFM	1
VAV-2-6	2P-117, 2P-118	-35 CFM	1
VAV-2-7	2P-113, 2P-112A	+65 CFM	1
VAV-2-8	2R-107, 2R-106A	+50 CFM	1
VAV-2-9	2V-135, C2-204	+100 CFM	1

1. CHANGE IN TOTAL BOX CFM IS BASED ON PRELIMINARY AIR QUANTITIES PREVIOUSLY MEASURED. CONTRACTOR TO MEASURE AND BALANCE ALL BOXES AND DIFFUSERS TO EXISTING AIR QUANTITIES OR NEW AS INDICATED.

100% CD ISSUE
FULLY SPRINKLERED

REVISIONS	ADDENDUM #3	02/18/13
REVISIONS	ADDENDUM #1	02/05/13
REVISIONS	DATE	


GENERAL NOTES:

GENERAL CONTRACTOR AND/OR ALL SUBCONTRACTORS SHALL FIELD VERIFY ALL DIMENSIONS SHOWN ON THESE PLANS AND SHALL BE RESPONSIBLE FOR VARIATIONS BETWEEN PLAN DIMENSIONS AND ACTUAL FIELD DIMENSIONS. WHERE VARIATIONS ARE FOUND TO OCCUR, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING PRIOR TO PROCEEDING WITH CONSTRUCTION; NO ADJUSTMENT TO THE WORK WILL BE MADE WITHOUT THE PRIOR APPROVAL OF THE PROJECT ENGINEER.

GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR GENERAL DEMOLITION INCLUDING REMOVAL OF WALLS, PARTITIONS, DOORS & CEILING & FLOORS. ANY AND ALL CUTTING OF CONCRETE FLOORS, WALLS OR STRUCTURE SHALL BE THE GENERAL CONTRACTOR'S RESPONSIBILITY. CORE DRILLING THROUGH CONCRETE WALLS, FLOORS OR STRUCTURE FOR PIPING OR CONDUIT SHALL BE THE RESPONSIBILITY OF THE SUBCONTRACTOR BY TRADE. FIRESTOPPING OF THESE OPENINGS SHALL BE DONE BY THE RESPECTIVE SUBCONTRACTOR. REMOVAL OF DEBRIS RESULTING FROM DEMOLITION, CUTTING, AND/OR DRILLING IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR. PATCHING AND REPAIR OF CONCRETE WALLS, FLOOR, OR STRUCTURE SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR; THIS WILL BE ACCOMPLISHED UPON COMPLETION OF THE INSTALLATION OF ANY AND ALL UTILITIES INSTALLED BY THE VARIOUS SUBCONTRACTORS.

DUNHAM

Dunham Associates, Inc.
50 South Sixth Street / Suite 1100
Minneapolis, Minnesota 55402-1540
PHONE 612.465.7550 FAX 612.465.7551
WEB dunhameng.com
mechanical + electrical consulting engineering



I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Engineer under the laws of the State of Minnesota.

DARIN MAY
Date 08/13/2012 Reg. No. 42401

Drawing Scale
AS NOTED

Plot Scale
12" = 1'-0"

Drawing Title
SECOND FLOOR MECHANICAL SPD SATELLITE ROOMS PLANS

Approved: Cynthia Doolittle, Chief, Projects Section

Approved: Steven Challeen, Director, Engineering

Project Title
VA SPD HVAC IMPROVEMENTS

Location **V.A. MEDICAL CENTER ONE VETERANS DRIVE MINNEAPOLIS, MN 55417**

Date **08/13/2012**

Checked CM

Drawn AU

Project No.
618-12-127

Building Number
70

DRAWING NO.
1260-M11

Dwg. **18 OF 28**

Office of
Facilities
Management

Department of
Veterans Affairs